

WORKS ON ROADS TRAFFIC MANAGEMENT PLAN

Work Type: MAINTENANCE
TMP Number: TMP-2025-E4450FA3
Date: 19/11/2025

DECLARATION

I, Grant Mckenzie (AWTM Cert No. AWTM-TBC) declare that I have designed this Traffic Management Plan following a site inspection on 19/11/2025.
This Traffic Management Plan has been prepared in accordance with the Main Roads Code of Practice, AGTTM and AS 1742.3

Signature: Date: 19/11/2025

TABLE OF CONTENTS

Section	Title	Page
1	Introduction	6
2	Project Overview	7
3	Risk Management	10
4	Traffic Management Planning and Assessment	16
5	Site Assessment	19
6	Safety Plan	21
7	Implementation	26
8	Emergency Arrangements and Contingencies	30
9	Monitoring and Measurement	33
10	Management Review and Approvals	35

1. INTRODUCTION

1.1 Purpose and Scope

This Traffic Management Plan (TMP) has been prepared for repave footpath with pavers and cu8rbs ass required on 185 Torrens Road Ridleyton.
The scope includes maintenance activities from 2025-11-24 to 2025-11-28.

1.2 Objectives and Strategies

Objectives:

- Safety of road workers
- Safe guidance of all road users
- Minimal network impact
- Minimized disruption and inconvenience
- Minimized impact on adjacent properties

Strategies:

- Implement temporary speed reduction
- Maintain safe access for all road users
- Minimize work zone length and duration
- Provide clear advance warning of work activities

2. PROJECT OVERVIEW

2.1 Location

Works located between 185 Torrens Road Ridleyton and 197 Torrens Road Ridleyton

2.2 Project Details

Item	Details
Project Location	185 Torrens Road Ridleyton
Road Classification	Major Urban Arterial
Existing Speed Limit	60 km/h
Road Authority	Local Council
Principal Contractor	Funked Up Conglomerate PTY LTD
Scope of Works	repace footpath with pavers and cu8rbs ass required
Project Dates	2025-11-24 to 2025-11-28
Work Hours	Standard hours: 7:00 AM to 6:00 PM, Monday to Friday

3. RISK MANAGEMENT

3.1 Risk Classification

Risk assessment follows the qualitative risk matrix approach with consequence and likelihood ratings.

3.2 Risk Register

Risk Event	Consequence	Pre-Treatment Risk	Treatment	Residual Risk
Vehicle collision with worker	Major injury or fatality	High	Physical barriers, high-vis clothing, traffic control	Medium

Vehicle collision in work zone	Property damage, injury	High	Clear signage, adequate warning distance	Advance, traffic control
--------------------------------	-------------------------	------	--	--------------------------

7. IMPLEMENTATION

7.1 Traffic Guidance Schemes

Stage 1: Initial setup and lane closure

7.2 Sequence and Staging

Stage 1 - Setup:

Install advance warning signs and initial traffic control

Safety Measures: Use of safety vehicles and trained personnel

Stage 2 - Work Phase:

Maintain traffic control throughout work activities

Safety Measures: Continuous monitoring and adjustment as required

Stage 3 - Removal:

Safe removal of all temporary devices

Safety Measures: Systematic removal in reverse order of installation

8. EMERGENCY ARRANGEMENTS

8.5 Emergency Contacts

Service	Contact
Police	000
Ambulance	000
Fire	000
Road Authority	TBC
Project Manager	0424283667

This Traffic Management Plan has been prepared in accordance with:

- Main Roads Code of Practice
- AGTTM
- AS 1742.3

Generated: 19 November 2025 at 12:18 PM

Template Version: March 2025 edition