

WORKS ON ROADS TRAFFIC MANAGEMENT PLAN

Work Type: MAINTENANCE
TMP Number: TMP-2025-E4679273
Date: 14/12/2025

DECLARATION

I, (AWTM Cert No. AWTM-TBC) declare that I have designed this Traffic Management Plan following a site inspection on 14/12/2025.
This Traffic Management Plan has been prepared in accordance with the Main Roads Code of Practice, AGTTM and AS 1742.3

Signature: Date: 14/12/2025

TABLE OF CONTENTS

Section	Title	Page
1	Introduction	6
2	Project Overview	7
3	Risk Management	10
4	Traffic Management Planning and Assessment	16
5	Site Assessment	19
6	Safety Plan	21
7	Implementation	26
8	Emergency Arrangements and Contingencies	30
9	Monitoring and Measurement	33
10	Management Review and Approvals	35

1. INTRODUCTION

1.1 Purpose and Scope

This Traffic Management Plan (TMP) has been prepared for Planned maintenance static works on 506 tappleys hill road (National Highway). Traffic management in accordance with AS 1742.3 and AGTTM. on 506 tappleys hill road, fulham Gardens .
The scope includes maintenance activities from 2026-01-20 to 2026-01-23.

1.2 Objectives and Strategies

Objectives:

- Safety of road workers
- Safe guidance of all road users
- Minimal network impact
- Minimized disruption and inconvenience
- Minimized impact on adjacent properties

Strategies:

- Implement temporary speed reduction
- Maintain safe access for all road users
- Minimize work zone length and duration
- Provide clear advance warning of work activities

2. PROJECT OVERVIEW

2.1 Location

Works located between 506 tappleys hill road, fulham Gardens and 480 Tapleys hill road, Fulham Gardens

2.2 Project Details

Item	Details
Project Location	506 tappleys hill road, fulham Gardens
Road Classification	National Highway
Existing Speed Limit	60 km/h
Road Authority	National Transport Commission / State Government
Principal Contractor	test
Scope of Works	Planned maintenance static works on 506 tappleys hill road (National Highway). Tr
Project Dates	2026-01-20 to 2026-01-23
Work Hours	Standard hours: 7:00 AM to 6:00 PM, Monday to Friday

3. RISK MANAGEMENT

3.1 Risk Classification

Risk assessment follows the qualitative risk matrix approach with consequence and likelihood ratings.

3.1.1 Risk Matrix

Likelihood → Consequence ↓	Insignificant (1)	Minor (2)	Moderate (3)	Major (4)	Catastrophic (5)
Almost Certain (5)	Medium	High	High	Extreme	Extreme
Likely (4)	Medium	Medium	High	High	Extreme
Possible (3)	Low	Medium	Medium	High	Extreme
Unlikely (2)	Low	Low	Medium	Medium	High
Rare (1)	Low	Low	Low	Medium	Medium

Risk Level Definitions:

- **Extreme:** Immediate action required. Work cannot proceed until controls are implemented.
- **High:** Senior management attention needed. Implement additional controls before proceeding.
- **Medium:** Management responsibility specified. Timeframe for risk reduction established.
- **Low:** Manage by routine procedures. Monitor and review controls regularly.

3.2 Risk Register

Risk Event	Consequence	Pre-Treatment Risk	Treatment	Residual Risk
Vehicle collision with worker	Major injury or fatality	High	Physical barriers, high-vis clothing, traffic control	Medium
Vehicle collision in work zone	Property damage, injury	High	Clear signage, adequate warning distance, traffic control	Low

7. IMPLEMENTATION

7.1 Traffic Guidance Schemes

Stage 1: Initial setup and lane closure

7.2 Sequence and Staging

Stage 1 - Setup:

Install advance warning signs and initial traffic control

Safety Measures: Use of safety vehicles and trained personnel

Stage 2 - Work Phase:

Maintain traffic control throughout work activities

Safety Measures: Continuous monitoring and adjustment as required

Stage 3 - Removal:

Safe removal of all temporary devices

Safety Measures: Systematic removal in reverse order of installation

8. EMERGENCY ARRANGEMENTS

8.5 Emergency Contacts

Service	Contact
---------	---------

Police	000
Ambulance	000
Fire	000
Road Authority	TBC
Project Manager	

This Traffic Management Plan has been prepared in accordance with:

- Main Roads Code of Practice
- AGTTM
- AS 1742.3

Generated: 14 December 2025 at 06:27 AM
Template Version: March 2025 edition