

WORKS ON ROADS TRAFFIC MANAGEMENT PLAN

Work Type: CONSTRUCTION
TMP Number: TMP-2025-FAA5EEC5
Date: 19/10/2025

DECLARATION

I, Sarah Williams (AWTM Cert No. AWTM-TBC) declare that I have designed this Traffic Management Plan following a site inspection on 19/10/2025.
This Traffic Management Plan has been prepared in accordance with the Main Roads Code of Practice, AGTTM and AS 1742.3

Signature: Date: 19/10/2025

TABLE OF CONTENTS

Section	Title	Page
1	Introduction	6
2	Project Overview	7
3	Risk Management	10
4	Traffic Management Planning and Assessment	16
5	Site Assessment	19
6	Safety Plan	21
7	Implementation	26
8	Emergency Arrangements and Contingencies	30
9	Monitoring and Measurement	33
10	Management Review and Approvals	35

1. INTRODUCTION

1.1 Purpose and Scope

This Traffic Management Plan (TMP) has been prepared for Comprehensive traffic management for Torrens Road Ridleyton - Complete Closure with Detour on 185 Torrens Road Ridleyton.
The scope includes Construction activities from 2025-10-26 to 2025-11-09.

1.2 Objectives and Strategies

Objectives:

- Safety of road workers
- Safe guidance of all road users
- Minimal network impact
- Minimized disruption and inconvenience
- Minimized impact on adjacent properties

Strategies:

- Maintain safe access for all road users
- Minimize work zone length and duration
- Provide clear advance warning of work activities

2. PROJECT OVERVIEW

2.1 Location

Works located between 185 Torrens Road Ridleyton and 195 Torrens Road Ridleyton

2.2 Project Details

Item	Details
Project Location	185 Torrens Road Ridleyton
Road Classification	Major Urban Arterial
Existing Speed Limit	60 km/h
Road Authority	Local Council
Principal Contractor	Complete TMP Solutions Pty Ltd
Scope of Works	Comprehensive traffic management for Torrens Road Ridleyton - Complete Closure
Project Dates	2025-10-26 to 2025-11-09
Work Hours	Standard hours: 7:00 AM to 6:00 PM, Monday to Friday

3. RISK MANAGEMENT

3.1 Risk Classification

Risk assessment follows the qualitative risk matrix approach with consequence and likelihood ratings.

3.2 Risk Register

Risk Event	Consequence	Pre-Treatment Risk	Treatment	Residual Risk
Vehicle collision with worker	Major injury or fatality	High	Physical barriers, high-vis clothing, traffic control	Medium
Vehicle collision in work zone	Property damage, injury	High	Clear signage, adequate warning distance, traffic control	Low

TRAFFIC GUIDANCE SCHEMES

The following traffic control devices have been positioned according to Austroads standards:

Device Type	Device Name	Position	Compliance
Warning	Road Work Ahead	Lat: -34.889949, Lng: 138.571945	Manual placement

7. IMPLEMENTATION

7.1 Traffic Guidance Schemes

Stage 1: Initial setup and lane closure

7.2 Sequence and Staging

Stage 1 - Setup:

Install advance warning signs and initial traffic control
Safety Measures: Use of safety vehicles and trained personnel

Stage 2 - Work Phase:

Maintain traffic control throughout work activities
Safety Measures: Continuous monitoring and adjustment as required

Stage 3 - Removal:

Safe removal of all temporary devices
Safety Measures: Systematic removal in reverse order of installation

8. EMERGENCY ARRANGEMENTS

8.5 Emergency Contacts

Service	Contact
Police	000
Ambulance	000
Fire	000
Road Authority	TBC
Project Manager	08 8123 4567

This Traffic Management Plan has been prepared in accordance with:

- Main Roads Code of Practice
- AGTTM
- AS 1742.3

Template Version: March 2025 edition